



**ADDITIONS AND ALTERATIONS TO EXISTING
BUILDING TO ACCOMMODATE
JOHNSON CITY JUVENILE COURT
607 – 609 MYRTLE AVENUE
JOHNSON CITY, TENNESSEE
TWA PROJECT 011-049**

12-18-12

December 18, 2012

ADDENDUM NO. 2

1. General Items:

- a. The existing building will be open and available for examination on the following dates and times:

Wednesday, December 19, 2012; 10:00 am – thru 12:00 pm.

Friday, December 21, 2012; 10:00 am – thru 12:00 pm.

Monday, December 24, 2012; 10:00 am – thru 12:00 pm.

Wednesday, December 26, 2012; 10:00 am – thru 12:00 pm.

Friday, December 28, 2012; 10:00 am – thru 12:00 pm.

Contact Samuel (Sonny) Hughes (office 423-975-2554, cell 423-483-5925) with questions about building access.

2. Refer to Specifications Section 02 2520 Portland Cement Concrete Pavement:

- a. Refer to paragraph 2.01, A-1: Concrete for sidewalks is to be 4,000 psi for 28 day design mix.

3. Refer to Specifications Section 07 4113 Metal Roof Panels:

- a. Refer to paragraph 2.1, A; add MRS System to the list of approved manufacturers.

4. Refer to Drawing C3-1:

- a. Refer to Detail 4 / C3-1: Concrete for sidewalks is to be 4,000 psi for 28 day design mix.

5. Refer to Drawing A-24:

- a. Refer to Detail 8 / A-24: plywood wall sheathing indicated on 2X blocking between roof deck and eave to be 5/8" thick, exterior grade.

END OF ADDENDUM NO. 2